



B10 AND B15 SERIES

COMBINATION CLEANING/VACUUMING MACHINES



The B10 and B15 Combination Cleaners are designed to give unsurpassed performance in catch basins, storm sewers, lift stations and treatment plants in municipal and industrial applications.



SOME FEATURES SHOWN MAY BE OPTIONAL.


HIGH-PERFORMANCE, STATE-OF-THE-ART FEATURES INCREASE PRODUCTIVITY.

- **SINGLE ENGINE DRIVE**
Dramatically decreases fuel consumption, maintenance expenses, sound levels, weight on chassis and initial purchase price. Chassis engine powers all systems.
- **REAR MOUNTED HOSE REEL**
The 180° articulating rear reel facilitates placement of unit regardless of manhole location. The rear location assures unobstructed vision for the driver, allows maximum air flow to the chassis engine and provides the quietest workstation in the industry.
- **FULL POWER. 360° ROTATING BOOM**
The top loading boom is self-cleaning, powers up/down and extends to 20 feet. Top mounting produces even load distribution.
- **VACUUM HOSE**
The heavy-duty, wire-reinforced rubber, 8" hose is designed to prevent wear and clogging. Vacuums up bottles, cans and bricks over 150 feet in depth.
- **CYLINDRICAL DEBRIS TANK**
High-strength steel is corrosion and abrasion-resistant. Has more usable space for larger loads than any other design. Capacities of 10 to 15 cu. yds.
- **LIGHTWEIGHT WATER TANKS**
Fully baffled 3/8" thick, U.V. stabilized, non-corrosive polyethylene saddle tanks. Capacities from 1000 to 1500 gallons.

- **TRIPLEX RECIPROCATING WATER PUMP**
Continuous flow triplex reciprocating water pump is rated at up to 80 GPM@2500 psi and is designed to operate dry.
- **INTERNAL BOOM VALVE**
Increases air velocity, builds instantaneous vacuum to 204" of negative water pressure for picking up materials above and below water.
- **VACUUM CUT-OFF SYSTEM**
Fail safe protection prevents materials from entering positive displacement exhauster and passing into the atmosphere.
- **LOWEST CENTER OF GRAVITY**
Makes full loads more stable during transport.
- **PNEUMATIC FOOT CONTROL**
Permits one-man operation of hose reel payout/retrieve, and allows operator to work any distance from unit.
- **VACUUM TUBES**
Ball and socket connections and quick-acting lever locks from a water-tight seal. Tubes can be locked at various angles to allow infinite positioning of tubes when cleaning deep manholes and catch basins.


DISTRIBUTED BY:

■ Combination Machine ■ Rear Mounted Reel



Dimensions	B10		B15	
	U.S.	Metric	U.S.	Metric
A. Overall length	267"	6782 mm	331"	8407 mm
B. Height above truck frame	103"	2616 mm	103"	2616 mm
C. Overallwidth	98"	2489 mm	98"	2489 mm

Dimensions may vary with chassis and options selected. Specifications are subject to change without notice.
All ratings are calculated at sea level. Patents applied for. Some features may be optional.



180° ARTICULATION
(TOP VIEW)

GENERAL DESCRIPTION

AIR/VAC SYSTEM

Positive displacement exhauster
2700 CFM (4588 m³/h) operating capacity,
204" (5282 mm) water column
Poly chain drive
Muffler silencer
Protected by micro-filter/centrifugal separator
Vacuum relief valves

DEBRIS TANK

Cylindrical design
10 cu. yd. (7.6 m³) B10
15 cu. yd. (11.5 m³) B15
Dumping 45°
Hydraulic power up/down cylinder
Self-aligning closure seal
Top-hinged full opening rear door
Two 5" (127 mm) liquid level sight eyes
Debris deflector plate
Double strainer for rear door drain
Rear door security prop
4 mechanical rear door locks
Rear door power up/down hydraulic cylinder
Stainless steel ball check valve
6" (152 mm) quick opening rear drain valve
6" (152 mm) x 15" (4.6 m) lay flat discharge

BOOM

Top mounted
360° hydraulic rotation
Portable pendant, controls all functions
Internal boom valve
8" (203 mm) extra heavy duty rubber intake hose
Extends to 20' (6.1 m)
Powers up/down
Rear storage location
Quick open cleanout

WATER SYSTEM

Triplex reciprocating
80 GPM (303 liters)
2500 PSI (172 bar)
Poly chain drive
Pressure relief valve
Water flow control valve
Air valve on pump for cold weather operation
Wash down gun connection
Wash down gun with 35' (10.7 m) of 1/2" (12.7 mm) hose
Printed in U.S.A.

@1999 Aquatech, Inc.
@Hi Vac Corporation
CPC 6-08

800 PSI (55 bar) relief valve
Suction strainer

WATER TANK

B10 1000 gal. (3785 liters)
B15 1500 gal. (5677 liters)
Saddles tanks independent of debris tank
Material: U.V. stabilized 3/8" (9.5 mm) thick
Fully baffled
Anti-siphon air gap protection
Curb side fill
2 liquid level indicators
Removable inspection covers
Limited lifetime warranty

HOSE REEL

Rear mounted
Hydraulic 180° articulating
400' (122 m) of 1" (25.4 mm), 2500 PSI (172 bar) hose
800' of 1" (248 m) hose capacity
Reel speed control valve
Hose levelwind
Hydraulic drive
Pneumatic food control pedals
Automatic positioning lock
Engine throttle
Vacuum/pressure gauge
Tachometer
Water pressure gauge

POWER TAKE-OFF

Split shaft transfer case
Pneumatic shifting

ACCESSORIES, STANDARD

Hinged tank support prop
8" x 8" (203 mm x 2.4 m) aluminum extension tube
8" x 6" (203 mm x 1.8 m) aluminum intake tube
Two operation, parts and service manuals (unit only)
15° nozzle
35° nozzle
Manhole hose guide
Painted one color, acrylic enamel
Touch-up paint
2 aluminum tool boxes
Tube storage carriers on front bumper
Aluminum fenders
Mud flaps

VACUUM/DEBRIS TANK OPTIONS

Hydraulic rear door locks
Water pump-off system
Internal flush-out system
Exhausters up to 4500 CFM
Telescoping boom to 25' (7.6 m)
Waste-water recycling
Fluidizer for underwater suction
Stainless steel tank
Tank vibrator

WATER SYSTEM OPTIONS

Cold weather recirculation
Rubber leader hose
35-160 GPM (132-605 liters) water pumps
Pressure: 0-3000 psi (207 bar)
1/2" (12.7 mm) hose reel
Pulsation dampener
Increased water capacity

OTHER OPTIONS

Front mounted hose reel
Power tilt for front mounted hose reel
Front mounted extending 320° rotating rose reel
Counter for levelwind
Street flushers
Debris and water tank interconnect
Deluxe tube storage racks
Power deck shroud and skirting
Body arrow light board

For other options, see Aquatech's accessory catalog.
Specifications are subject to change without notice.
Some photographs may show optional equipment.
All ratings are calculated at sea level.
Patents applied for.



CORPORATE HEADQUARTERS
4713 Gettysburg Rd | Mechanicsburg, PA 17055

800.626.7835 sweeperland.com